

CORRIGENDUM

Dt.- 20.01.2021

With reference to the tender naming "SUPPLY,ERECTION AND INSTALLATION OF SIGNAGES IN AND AROUND UNIVERSITY CAMPUS AT NLUO", Cuttack. Vide no. TENDER NO. NLUO/AR-II/01/21.

The following changes are made:-

1. Cost of EMD - ₹.6,000.00(Six Thousand only) in stead of ₹.6,00.00(Six Hundred only)
- 2.

Last date & time of receipt of Quotation	28.01.2021 at 11.00 AM
Date & time of opening of Quotation	28.01.2021 at 11.15 AM

3. Revised Price bid as per Annx.-I(As enclosed with this file is to be filled up & submitted)

ANNEXURE-I

SCHEDULE

Name of the work: SUPPLY, ERECTION AND INSTALLATION OF SIGNAGES IN AND AROUND UNIVERSITY CAMPUS at NLUO, Cuttack.

<u>Sl.</u>	<u>Description</u>	<u>Qty</u>	<u>Unit</u>	<u>Rate</u>	<u>Amount</u>
1	Providing and applying white cement based putty, of approved brand and manufacturer, over the existing wall surface to prepare the surface even and smooth with exterior texture paint of approved colour and design by removing the ACP/cladding (if any) and making preparation of smooth even surface by arranging all material, labour and all necessary things to make the surface ready by one or more necessary coats on old work along with removing old paint by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. Complete for fixing of stainless steel letter blocks all complete as per specification and direction of Engineer—in-charge.	1000.00	One Square Feet		
2	Manufacturing, supplying and fixing of stainless steel letter(English) blocks of height of 24 inches of Arial font made up of 304 grade (3 mm thick) 18 gauze thick finished plates of matt/gloss/mirror finished box type letters with side raising of 01 inch and fixing the same with suitable sized alloy rivets &/ bolting system to back support frame mounting on existing poles &/ surface or as directed with nut bolts arrangement and welding, with scaffolding other tools and tackles etc. to make it Complete as per specification and direction of Engineer—in-charge to match the existing displayed letters if any.	19.00	Each		
3	Manufacturing, supplying and fixing of stainless steel letter(English) blocks of height of 30 inches of Arial font made up of 304 grade 3 mm thick 18 gauze thick finished plates of matt/gloss/mirror finished box type letters with side raising of 01 inch and fixing the same with suitable sized alloy rivets &/ bolting system to back support frame mounting on existing poles &/ surface or as directed with nut bolts arrangement and welding, with scaffolding other tools and tackles etc. to make it Complete as per specification and direction of Engineer—in-charge to match the existing displayed letters if any.	30.00	Each		
4	Manufacturing, supplying and fixing retro reflective stickers (English) made up of 3M stickers of 24 inches height of Arial Font suitably in the shades of Blue pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure fixing the same with back support frame of ACP mounting on existing poles or as directed with arrangements for scaffolding other tools and tackles etc. to make it Complete as per specification and direction of Engineer—in-charge to match the existing displayed letters if any.	13.00	Each		
5	Providing & fixing 10W LED COB spike (Wipro/KWW or equivalent) of required warm/daylight/ coloured light(preferably in the shades of blue) to be fixed in MS iron frames(cost of frame will be paid as per sl no. 07) to be installed as stands along with wiring for lights with appropriate protection system all complete, as directed by Engineer-in-charge.	20.00	Each		
6	Manufacturing, supplying and fixing of stainless steel letter blocks(English/Odia) of height of 15 inches of Arial font made up of 304 grade 3 mm thick 18 gauze thick finished plates of matt/gloss/mirror finished box type letters with side raising of 01 inch and fixing the same with suitable sized alloy rivets &/ bolting system to back support frame mounting on existing poles &/ surface or as directed with nut bolts arrangement and welding, with scaffolding other tools and tackles etc. to make it Complete as per specification and direction of Engineer—in-charge to match the existing displayed letters if any.	18.00	Each		
7	Provision of MS iron frames to be installed as stands for LED lights with all provision Complete as per site condition and direction of Engineer—in-charge at all heights.		Lumpsum		
				TOTAL =	

Grand Total (in word).....

*In case of ambiguity in rate quoted & amount mentioned, lowest among them will only be considered.

No. of Corrections :

No. of Over writings:

NOTE:-Bidders are required to quote against each item legibly and arrive at the total cost of work. All pages should be duly signed by the bidder failing which the bid may be rejected.

SIGNATURE OF BIDDER WITH STAMP